

## City of Covington Storm Sewer Cleaning Contract

### SCOPE OF SERVICES

The Contractor agrees to provide storm sewer cleaning services during this contract as follows.

- **2010** All Catch Basins – Type I and II (approximately 500) and all Retention Facilities – Type II (approximately 50) in **Maintenance Zone 1** will be vactored and operational. All storm filter vaults (approximately 6) will be cleaned and filters replaced (see item 8 below).
- **2011** All Catch Basins – Type I and II (approximately 500) and all Retention Facilities – Type II (approximately 50) in **Maintenance Zone 2 and Maintenance Zone 3** will be vactored and operational.
- **2012** All Catch Basins – Type I and II (approximately 500) and all Retention Facilities – Type II (approximately 50) in **Maintenance Zone 4** will be vactored and operational.

NOTE: There are approximately a total of 1,500 Type I and Type II catch basins in the identified Maintenance Zones of the City to be cleaned. The actual number of catch basins will vary, but is not expected to exceed 2,000 and not expected to exceed 700 per Maintenance Zone.

Contractor will perform the following:

1. Contractor will provide all necessary labor, material, and equipment to perform the work described herein.
2. Contractor will follow a systematic route cleaning all Type I and Type II Catch Basins within the identified area, including Retention Facilities and Storm Filter Vaults.
3. Contractor will log, on a road map approved by the City of Covington Maintenance Supervisor, the location of Type I and Type II Catch Basins that have been cleaned and indicate the direction of storm water flow from catch basin to catch basin. Contractor will prepare a map in electronic format identifying the location of each catch basin.
4. Once a catch basin is cleaned, contractor will mark the grate with permanent white paint in a manner directed by the City of Covington Maintenance Supervisor.
5. Before leaving each catch basin location, contractor will clean all catch basin grates and/or lids with high-pressure water.

6. Contractor will transfer decant to a Department of Ecology approved decant station only. No decant will be pumped or drained back into the catch basin or storm system.
7. Contractor will provide monthly verification of proper disposal of spoils.
8. Filter Maintenance: Storm vaults containing filters will be cleaned as requested by the City. Filters will be replaced during this process using proprietary filters provided by the City.
9. Contractor will provide emergency response 24 hours a day upon request of the City.
10. Contractor will notify the City of Covington Maintenance Supervisor in advance of work schedules.
11. Contractor will provide a weekly log to the City of Covington Maintenance Supervisor via email or fax indicating completed work.
12. The City of Covington shall be invoiced within 30 days of completion of work.