

## DETAIL NOTES

Saw-cut opening should not be larger than 12" beyond the radius of the cover.

Remove base material, surfacing course, and frame, then add appropriate risers, replace frame and cover at finished grade of pavement, adjusted to match the centerline grade and cross-slope.

For significant adjustment (>6"), a rectangular adjustment section shall be used. For minor adjustments, concrete brick shall be used. Adjustment sections, brick and frame shall be mortared in place.

Fill and mechanically compact around the structure and frame with Asphalt Concrete Pavement (ACP) to finished grade, or with crushed surfacing top course to within one inch below existing asphalt from finished grade and filling the remaining space with ACP.

All joints shall be grouted, inside and out, after the frame has been placed.


Final adjustment of all covers and access entries shall be completed within 30 days of final paving.



City of Covington

Public Works

Community Development



## FRAME AND COVER ADJUSTMENT

This document has been signed electronically in accordance with WAC 196-23-070 and Chapter 19.34 RCW. Unauthorized alteration of any of the information on this document will invalidate the document, my certification and signature.

729

Revision Date  
October 2009